

1429 Centre Circle Drive Downers Grove, IL 60515 Phone: (630) 691-8271 Fax: (630) 691-1819

E-Mail: uasinc@uas1.com

November 21, 2017

Park Ridge-Niles School District #64 164 S. Prospect Avenue Park Ridge, Illinois 60068

UAS Project 1798565-01

Attn: Mr. Ron DeGeorge, Director of Building and Grounds

Summary of Findings - Lead in Drinking Water Sampling & Lab Analysis Re:

Park Ridge - Niles School District #64

Washington School -

1500 Stewart Avenue, Park Ridge, Illinois 60068

November 1, 2017

Dear Mr. DeGeorge:

United Analytical Services, Inc. (UAS) prepared this executive summary of findings for the drinking water sampling performed at Park Ridge-Niles School District #64's Washington School located at 1500 Stewart Avenue in Park Ridge, Illinois on November 1, 2017. The current testing involved collecting drinking water samples from ALL twenty-five (25) of the drinking water sources/locations throughout the school facility that are accessible to the Students, Faculty and Staff, with subsequent laboratory analysis for the presence of Lead. Including 1st draw and 2nd draw samples at each of the drinking water sources, a total of fifty (50) water samples were collected during this current assessment.

It should be noted that at the request of Park Ridge-Niles School District #64, the current sampling included the IDPH required drinking water sources within facility, as well as a number of non-required drinking water and/or potable water sources within the school building.

The laboratory results reveal that the reported concentrations for fifty (50) of the fifty (50) drinking water samples resulted in concentrations below the IDPH public notification/communication target level of 5 µg Lead/L. Zero (0) of the fifty (50) samples revealed a drinking water concentration above the IDPH public notification/communication target level of 5 µg Lead/L.

SAMPLING REQUIREMENTS AND METHODOLOGY -

The current sampling and reporting followed the Illinois Public Act 99-0922 requirements, Following the IDPH requirements and reporting, it should be noted that UAS performed and provided the services noted below, including, but not limited to, the following:

Mr. Ron DeGeorge, Director of Building and Grounds Summary of Findings - Lead in Drinking Water Sampling & Lab Analysis Park Ridge - Niles School District #64 Washington School -1500 Stewart Avenue, Park Ridge, Illinois 60068

- 1. The current testing and analysis was limited only to those twenty-five (25) locations/sources noted.
- 2. UAS provided fixture/source identifiers for each of the sources/locations identified with alphanumeric identifiers for each fixture and sample.
- 3. UAS utilized sampling media (250 mL sample bottles) obtained from a State of Illinois Environmental Protection Agency (IEPA) accredited laboratory, labeled all sampling bottles with the alphanumeric identifiers and prepared a Chain of Custody form for samples.
- 4. The IEPA accredited laboratory that UAS utilized to perform the laboratory analysis for this project was Pace Analytical Services, LLC (Pace) of Minneapolis, MN. Pace is recognized by the IEPA as NELAP-Recognized Environmental Laboratory for Lead in Drinking Water. A copy of the SLI accreditation for the approved method is attached. UAS confirmed with SLI, that the IDPH required minimum reporting limit (MRL) and significant digits requested by IDPH could be utilized and documented. The MRL identified by IDPH, and utilized for this assessment was 2.00 μg Lead/L, or lower.
- 5. Following confirmation from Park Ridge-Niles School District #64 (S.D. #64) that each of the target drinking water sources/systems had been allowed a mandated stagnation period of eight (8) to eighteen (18) hours, UAS collected the required 1st Draw and 2nd Draw (30 second flush) drinking water samples from each drinking water fixture/source identified by S.D. #64. S.D. #64 reported that the last use of any of the sources/fixtures in the school was 8:00 p.m. on October 31, 2017, following a day of typical school occupancy and usage within the facility. The sample collection by UAS began at 6:15 a.m. on November 1, 2017 and was completed prior to any water use within the building.
- 6. UAS completed and compiled Chain of Custody forms for the school building samples.
- 7. UAS submitted the samples to Pace following strict Chain of Custody protocols.
- 8. UAS compiled this final summary report with results for this school using IDPH's guidance for reporting, data and information spreadsheet to ensure consistency and reliability.
- 10. All sampling, documentation and reporting was performed under the direct supervision of an Illinois Department of Public Health (IDPH) licensed Lead Inspector/Risk Assessor.

IDPH REPORTING & PUBLIC NOTIFICATION -

As required, IDPH Reporting and Public Notification requirements shall be the responsibility of Park Ridge-Niles School District #64. Please note the following: Illinois Public Act 099-0922: Within seven (7) days of receipt of these test results, the district/school must email all test results to IDPH. If any of the samples taken in the school exceed 5 parts per billion (μ g/L), the school district or chief school administrator, or the designee of the school district or chief school administrator, shall promptly provide an individual notification of the sampling results, via written or electronic communication, to the parents or legal guardians of all enrolled students and include the following information: the corresponding sampling location within the school building and the United States Environmental Protection Agency's website for information about lead in drinking water. If any of the samples taken at the school are at or below 5 parts per billion (μ g/L), notification may be made by posting on the schools website.

November 21, 2017 Page – 3 –

TEST RESULTS / SUMMARY OF FINDINGS-

The test results are noted in the attached Spreadsheet and Analytical Laboratory Reports. The current testing and analysis was limited only to those twenty-five (25) locations/sources noted. Review of the current testing laboratory data reveals the following:

The results from twenty-five (25) of the twenty-five (25) locations/sources reveled concentrations below both the IDPH mitigation strategies lower limit of 2 ppb, and below the IDPH public notification/communication target level of 5 µg Lead/L.

Zero (0) of the twenty-five (25) locations/sources reported concentrations at/above the IDPH mitigation strategies lower limit of 2 ppb, but below the IDPH public notification/communication target level of 5 µg Lead/L.

Zero (0) of the twenty-five (25) locations/sources revealed a drinking water concentration above the IDPH public notification/communication target level of 5 µg Lead/L.

Pursuant to Public Act 99-0922, the Illinois Plumbing Licensing Law (225 ILCS 320/35.5), the IDPH is required to provide guidance to schools concerning mitigation of hazards discovered by testing for lead in water. While Section 35.5 does not require mitigation, IDPH is requiring the mitigation strategies and requirements contained in their Guidance Document for Mitigating Lead in Schools (copy attached) to be followed for all plumbing fixtures identified with any level of lead. IDPH further notes that mitigation strategies should continue until subsequent testing indicates no lead is present in water.

RECOMMENDATIONS -

At this time, UAS recommends the following:

- 1. Along with their standard water programs, Park Ridge-Niles School District #64 should follow the IDPH reporting requirements, as well as the mitigation strategies and requirements contained in their Guidance Document for Mitigating Lead in Schools (copy attached) for the sources, locations and fixtures that were identified with lead greater than 2 parts per billion (μg/L). IDPH further notes that mitigation strategies should continue until subsequent testing indicates no lead (<2.00 ppb) is present in water. While not applicable at this school, it should be noted that any source, location and fixture that is identified with lead of 5 parts per billion (μg/L) or greater should be taken "off-line", either permanently, or until such time that mitigation and subsequent testing demonstrate that lead levels are within acceptable IDPH limits.
- 2. Park Ridge-Niles School District #64 should provide this report and results to IDPH in accordance with Illinois Public Act 099-0922.
- 3. Pursuant to Public Act 99-0922, the Illinois Plumbing Licensing Law (225 ILCS 320/35.5), the IDPH is required to provide guidance to schools concerning mitigation of hazards discovered by testing for lead in water. While Section 35.5 does not require mitigation, IDPH is requiring the mitigation strategies and requirements contained in their Guidance Document for Mitigating

Mr. Ron DeGeorge, Director of Building and Grounds Summary of Findings - Lead in Drinking Water Sampling & Lab Analysis Park Ridge - Niles School District #64 Washington School -1500 Stewart Avenue, Park Ridge, Illinois 60068

Lead in Schools (copy attached) to be followed for all plumbing fixtures identified with any level of lead. IDPH further notes that mitigation strategies should continue until subsequent testing indicates no lead (i.e. <2.00 ppb) is present in water.

Thank you for the continued opportunity to be of service to Park Ridge-Niles School District #64. If you have any questions regarding this information, please do not hesitate to contact our office.

Sincerely, UNITED ANALYTICAL SERVICES, INC.

Thad Daniels Director of Field Services Lead Risk Assessor (IL 001047)

attachments: IDPH Spreadsheet Summary of Lead in Drinking Water

11/20/17 Laboratory Report & COCs

IDPH Mitigation Strategies

UAS' Inspector/Sample Collector License & Accreditation

Pace Laboratory Accreditation

cc: Kevin E. Aikman, Ph.D., CIH, FAIHA (UAS)

S:\TD\IHReports\SD64.Washington.1798565-01.Report

				Samula						Time of		Cample				Donorting	
ISBE ID	Building	Building Description	Sample	Sample Time (12	Collected	Sample ID	Sample Location	Fixture Type	Date of Last	Last Use	Sample Type	Sample Volume	Laboratory Name	Analytical	Concentration	Reporting Limit	Notes
	ID		Date	HR Clock)	Ву	Number	Description		Use	(12 HR		(mL)		Method	(ug/L)	(ug/L)	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-01a	2nd Grade Hallway DWC Left	WF - Water Cooler	10/31/2017	Clock) 8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-01a	2nd Grade Hallway DWC Left	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-01b WS-02a	2nd Grade Hallway DWC Right	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-02b	2nd Grade Hallway DWC Right	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-03a	2nd Grade Hallway BFS	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-03b	2nd Grade Hallway BFS	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-04a	1st Grade Hallway DWC	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-04b	1st Grade Hallway DWC	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-05a	1st Grade Hallway BFS	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	ws	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-05b	1st Grade Hallway BFS	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-06a	Nurse's Office Wash Basin	S - Sink	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	1
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-06b	Nurse's Office Wash Basin	S - Sink	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	ws	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-07a	Nurse's Office Sink	S - Sink	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-07b	Nurse's Office Sink	S - Sink	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	1
14-016-0640-2012	ws	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-08a	Nurse's Office Sink	S - Sink	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-08b	Nurse's Office Sink	S - Sink	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-09a	4th Grade Hallway BFS	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-09b	4th Grade Hallway BFS	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-10a	Classroom 102 Wash Basin	S - Sink	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	ws	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-10b	Classroom 102 Wash Basin	S - Sink	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	ws	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-11a	Classroom 102 Sink	S - Sink	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	ws	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-11b	Classroom 102 Sink	S - Sink	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-12a	Classroom 101 Wash Basin	S - Sink	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-12b	Classroom 101 Wash Basin	S - Sink	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	ws	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-13a	Gymnasium Hallway DWC Right	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-13b	Gymnasium Hallway DWC Right	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-14a	Gymnasium Hallway BFS	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-14b	Gymnasium Hallway BFS	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-15a	Gymnasium Hallway DWC Left	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-15b	Gymnasium Hallway DWC Left	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-16a	Gymnasium Hallway DWC Left	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-16b	Gymnasium Hallway DWC Left	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-17a	Gymnasium Hallway DWC Left	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	ws	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-17b	Gymnasium Hallway DWC Left	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-18a	2nd Floor Hallway North DWC Left	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-18b	2nd Floor Hallway North DWC Left	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-19a	2nd Floor Hallway North BFS	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-19b	2nd Floor Hallway North BFS	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-20a	2nd Floor Hallway Outside 222 DWC	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-20b	2nd Floor Hallway Outside 222 DWC	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-21a	2nd Floor Hallway Outside 222 BFS	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-21b	2nd Floor Hallway Outside 222 BFS	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	ws	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-22a	2nd Floor 5th Grade Hallway DWC Right	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	

14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-22b	2nd Floor 5th Grade Hallway DWC Right	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-23a	2nd Floor 5th Grade Hailway DWC BFS	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-23b	2nd Floor 5th Grade Hallway DWC BFS	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-24a	2nd Floor 5th Grade Hallway DWC Left	WF - Water Cooler	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-24b	2nd Floor 5th Grade Hallway DWC Left	WF - Water Cooler	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-25a	Basement Teacher's Lounge Sink	S - Sink	10/31/2017	8:00 PM	First Draw	250	Pace Labs	EPA 200.8	<2.00	0.10	
14-016-0640-2012	WS	Washington Elem Sch	11/1/17	6:15 AM	IL 001047	WS-25b	Basement Teacher's Lounge Sink	S - Sink	10/31/2017	8:00 PM	Flush	250	Pace Labs	EPA 200.8	<2.00	0.10	

R = Right

L = Left

ND = None Detected

BFS = Bottle Filling Station